





Installation

Preliminary

Product tech. support:

support@wizardscreens.com 1-888-949-3667

First things

- READ INSTRUCTIONS BEFORE PROCEEDING.
- It is recommended to install screens after door installation.
- If concealed, screen unit must be removable and serviceable.

Unpackaging

- Screen should remained packaged until installation.
- Closely inspect product for damage.
- If there is damage, report to Wizard Screens with pictures immediately.

Preparation

- Ensure zippers are in housing endcap slots. Figure 1
- Do *not* remove 2 small track supports at top and bottom of pull bar *until* attaching the tracks. Figure 2
- Brakes must be disengaged when operating. Keep rivet pin in brake handle during installation. Figure 3

 Figure 3



Figure 1



Figure 2



Tools Required

























<u>Pencil</u>



Vacuum

Dry Silicone


Spray

DRY SILICONE

Shims



Step Ladder Drill



Level





Tape Measure



OPTIONAL




Mount Housing



- 1. Maneuver housing into position and ensure plumb.
- 2. Mark endcap screw holes, move housing, and predrill.
- 3. Affix housing with provided mounting screws at top.
- For bottom, repeat steps 2 & 3.
 Ensure plumb and free of twist. Use shims if necessary.

*NOTE: Wait to drive screws home until after tracks are fastened.

*Brake rivet *must* remain in handle until the very end of installation.



Measure, Cut, & Prep Tracks (SINGLE Screen)


1. On **zipper entry ends** of both tracks, countersink zipper path and de-burr.





2. Mallet track guide.

- 3. Measure from **housing** to **opposite end** at the bottom, middle, and top. Record *smallest* measurement and mark on floor.
- 4. Calculate final measurement:
 - 1) Inside/Reveal: Subtract **3/16"**.
 - 2) Surface: Add **25/32"**, then subtract **3/16"**.
 - 3) Alternatively, position receiver at bottom mark and mark at magnet holder.





5.

6. Cut upper and bottom tracks to identical length.


7. Pre-drill 1/8" holes @ 16" O/C into each track.



Measure, Cut, & Prep Tracks (DOUBLE Screens)

A View Towards **Excellence**

1. On **zipper entry ends** of both tracks, countersink zipper path and de-burr.







2. Mallet track guide.



- 4. Calculate final measurement
 - 1) Straight: Subtract 1/16" to accommodate track joiner.
 - 2) Corner: Subtract 1 3/8" to accommodate corner joiner.








- 6. Cut upper and lower tracks to **identical length**.
- 7. Repeat on other side.
- 8. Pre-drill 1/8" holes @ 16" O/C into each track.



Install Tracks and Receiver

 Remove lower track support. Feed lower track through the pull bar endcap and feed zipper into the track guide's zipper entry. Push track firm against the housing.
 Do not damage the zipper and mesh.





Track fits in as shown

- 2. Fasten lower track to housing endcap nub. Fasten level. Shim if necessary.
- 3. Repeat steps 1 & 2 for upper track.
- 4. Bring the pull-bar to the nearest pre-drilled hole. Fasten upper track 1/8" above pull bar. Fully retract, then draw to next hole. Repeat process until complete. This step ensures parallel and that zipper aligns well inside housing.
- 5. <u>Singles</u>: Position receiver against end of tracks and affix to surface (Inside mount shown).

CHECK:


Singles: Receiver and housing are **plumb** both ways.

Doubles: Housing and straight joiners/corner joiners are vertically aligned

plumb both ways.

Tracks level, parallel, and free of twist.

Recessed Application



- 2. Position channel level. Shim if necessary.
- 3. Prep and cut tracks.
- 4. Fasten lower track to housing endcap nub.
- 5. Place into the channel (may require 2 people).
- 6. Abide by standard steps otherwise where applicable.

*NOTE: Lower housing endcap and lower track does *not* require affixing.

**IMPORTANT NOTE: For exterior applications, especially if area is unprotected, note that recess channel and tracks are not weatherproof. Water Egress is the responsibility of the general contractor or builder.





Special Applications



Concealed Applications

• Screen housing and tracks must be easily removable in the event the screen requires servicing. Millwork must be removable where access is required.

Exterior Applications

- **IMPORTANT NOTE: For exterior applications, especially if area is unprotected, please note that recess channel and tracks are not weatherproof (see previous page). Water Egress is the responsibility of the general contractor or builder.
- Water drainage requirements:
 - Drill weep-holes into the tracks Figure 1.
 - It is good practice to dab pilot holes in surface with waterproof silicone before fastening with screws (surface mounted)

 Figure 1


%4" Weep Hole

Homeowner Training



Educate the homeowner:

- 1. Twist the brake handle **fully** when operating the screen.
- 2. Dirt must not be allowed to build up in tracks. Keep tracks clean with brush, cloth, or vacuum. Mesh may be vacuumed with upholstery brush.



3. Spray Silicone into the opening that the mesh slides in along the entire track.

Use *only* **dry silicone**. Frequency dependent upon season and location. Clean tracks first.

- 4. Do *not* use corrosive cleaners.
- Retract when not in use.

